

INVITATION TO BID
WARREN COUNTY R-III SCHOOL DISTRICT
302 KUHL AVENUE
WARRENTON, MISSOURI 63383
PHONE: 636-456-4311
FAX: 636-456-7687

1. All bids must be in writing and sealed. Bids must be received no later than 11:30 a.m. on June 22 2011, at which time they will be publicly opened. Bids will be awarded at the regular meeting of the Board of Education June 30, 2011. Envelopes containing bids should be marked "**HIGH SCHOOL BLEACHER AREA STORM DRAINS**".
2. If a bid is awarded, it will be given to the lowest and/or best bidder. Any and all bids may be rejected at the discretion of the Warren County R-III School District. The district does reserve the right to waive bidding irregularities.
3. A pre-bid walk through is required before submitting a bid to install drains. A walk through will be conducted on June 14, 2011 at 9:30 a.m.

District payment information: All invoices received by the last Friday of each month will be processed for payment in the following month. All payments must be approved by the Board of Education at the regular meeting. The Board meets the 2nd Thursday of each month. Checks are mailed on the 23rd of each month or prior business day if the 23rd falls on a holiday or weekend.

Example: Invoice received on May 30, 2011 will be submitted to the Board of Education Meeting on June 12, 2011. The check will be mailed June 23, 2011.

Should the same invoice be received May 31, 2011 it would be approved at the July Board meeting and mailed July 23.

Bill to address: Warren County R-III School District, 302 Kuhl Ave., Warrenton, MO 63383

Questions regarding bid specifications should be directed to Rob McDaniel at 636-456-4311 ext 3373

HIGH SCHOOL BLEACHER AREA STORM DRAIN

SPECIFICATIONS

General Description

Provide all labor and material to install 8 – 8inch diameter drain inlets below High School bleachers and extend piping beyond baseball outfield. Set drain lines to provide positive drainage at a slope of 1.5-2%. Back fill with appropriate material to provide base for pavement and/or seed and straw and rough grade within 3 inches of final grade or more if settling is anticipated. No seed/straw or asphalt repair to be included in this bid.

Detailed Description

- 1.** Saw cut entire length of asphalt area below bleachers and across access road leading to track/football field to a width of 6 feet.
- 2.** Remove asphalt between saw cuts and dispose of debris down the hill behind the High School baseball field.
- 3.** Excavate and haul soil from below bleachers and across access road only, to allow any excavated areas to be filled in with 1 inch clean limestone after installation of pipe to provide a solid base for re-paving. Excess soil may be dumped down the hill behind the High School baseball field.
- 4.** Excavate remaining trench with the intention to backfill with original soil.
- 5.** Provide 300 feet of 8 inch schedule 35 PVC pipe for the first portion of pipe and 700 feet of 10 inch schedule 35 PVC pipe with a remaining allowance for 8 inch diameter risers to be determined by the installer according to depth of main drain line. Provide 300 tons of 1 inch clean limestone to backfill asphalted areas.
- 6.** Provide 8 inch round cast iron grates set to most appropriate grade.
- 7.** Provide all necessary fittings such as Ts, 90s, couplers etc. needed to connect pipe with risers and make turns.
- 8.** Backfill all trenches with appropriate material.